

MYRESIDE STREET, CARNTYNE, GLASGOW	
<b>Description:</b>	Reclamation, Bulk Earthworks, Drainage and Roadworks
<b>Form of Contract:</b>	Client-Specific
<b>Duration:</b>	32 weeks
<b>Contract Value:</b>	£2,100,000
<b>Client:</b>	Bellway Homes
<b>Clients Representative:</b>	T Lawrie & Partners; Mason Evans Partnership

This project brought elements of reclamation, infrastructure and remediation. It was initially won in competitive tender and then extended into two further phases by negotiation.

The first activity on the contract was the removal of 35,000m<sup>3</sup> of existing concrete slabs and foundations, all of which was processed for re-use on the site. We then progressed to bulk excavation and filling of 130,000m<sup>3</sup> of mainly natural materials. The majority of the material excavated was re-used as structural fill, with the balance also retained on site in landscaping features.



During the excavation, we encountered and successfully addressed small volumes of contaminated soils and groundwater. Both were taken off site for disposal at licensed facilities.



The final phase of the project saw us construct the new main access roads, drainage, ducting and kerb logs to create access for the commencement of house building.

Although the site was relatively large, it was at times shared with others, including a grouting contractor and the various trades involved in house building. As Principal Contractor for the site, we implemented a number of controls to ensure that each organisation could progress their operations safely and in a co-ordinated fashion.