

HOUSING SITE INFRASTRUCTURE, REDDINGMUIRHEAD	
Description:	Earthworks and Infrastructure for Housing Development.
Form of Contract:	Client Specific
Duration:	54 weeks
Contract Value:	£3,100,000
Client:	Kier Homes
Clients Representative:	Wren & Bell



This substantial contract saw us continue our presence at Reddingmuirhead, where we had previously completed extensive earthworks and remediation for another Client. On this occasion, working for Kier Homes, we constructed the main drainage and access roads for a new housing development. The drainage extended up to 6 metres in depth and included a crossing of the adjacent Union Canal, two SUDS detention ponds and a relief storage tank some 5 miles from the main site.

On the roadworks front, we constructed 550m of new spine road within the development and also upgraded 500m of Reddingmuirhead Road, which forms the sole access into the site. Our scope included new street lighting and a new set of traffic lights at the junction of Reddingmuirhead Road with Shieldhill Road.

The improvement of Reddingmuirhead Road was carried out with due consideration to the residents who depend on continuous access to their properties along the east side of that route. We also took great care that our work carried no risk of silt or chemical pollution of the Union Canal.

