

SOUTH STREET, GLASGOW HARBOUR – PHASE 1	
Description:	Reclamation
Form of Contract:	Client - Specific
Duration:	5 weeks
Contract Value:	£260,000
Client:	Clydeport Properties
Clients Representative:	Capita Symonds

This typical reclamation project saw us break out and remove concrete floor slabs and heavily-reinforced foundations to a minimum depth of 1.5 metres below original ground level. Larger structures were removed below that nominal limit.

The excavated concrete was crushed and re-used on the site, either by spreading immediately or by stockpiling for later use elsewhere on the development. Reinforcing steel was taken off site for recycling.

